



- NOTES:**
1. SEE DWG. NO. 126 FOR NUMBER AND DIAMETER OF RODS REQUIRED.
 2. NO FLANGES ARE TO BE BURIED.
 3. AFTER INSTALLATION, TIE-RODS AND CLAMP ASSEMBLIES SHALL BE CLEANED AND THOROUGHLY COATED WITH ROYSTON LABORATORIES, INC. ROSKOTE PLASTIC NO. A 939 OR KOPERS CO., INC. BITUMASTIC SUPERSERVICE BLACK OR APPROVED EQUIVALENT.
 4. WHEN RESTRAINING FITTINGS TO STEEL CASING PIPE, THE RODS MUST BE WELDED DIRECTLY TO THE CASING - USE OF STAR BOLTS ARE PROHIBITED. CASING MUST BE FULLY WELDED THROUGHOUT ITS LENGTH AND BE A MINIMUM OF 30" IN LENGTH. AREA TO BE WELDED MUST BE COMPLETELY BARE AND FREE OF ANY COATING MATERIAL.

FULTON COUNTY STANDARD DETAIL 127
 THRUST RESTRAINTS: TIE-ROD INSTALLATION

DATE	REVISIONS	DATE	REVISIONS
8/08	NRR		

DGS/DRN /CHKD: CMS
 APPROVED: REW
 DATE: 12-2-05



FULTON COUNTY PUBLIC WORKS
 141 PRYOR ST. ATLANTA, GA. 30303
 404-612-7400 FAX: 404-224-0496

DRAWING NO.
 127