



DEPARTMENT OF PURCHASING & CONTRACT COMPLIANCE

**Winner 2000- 2008 Achievement of Excellence in Procurement Award
National Purchasing Institute**

Jerome Noble, Director



August 11, 2008

**Re: #08ITB62600K-JD – T243 Reynolds Road at Westlake Parkway
Intersection Improvement**

Dear Bidders:

Attached is one (1) copy of Addendum 2, hereby made a part of the above referenced **#08ITB62600K-JD-T243 Reynolds Road at Westlake Parkway Intersection Improvement**.

Except as provided herein, all terms and conditions in the **#08ITB62600K-JD-T243 Reynolds Road at Westlake Parkway Intersection Improvement** referenced above remain unchanged and in full force and effect.

Sincerely,

Joyce Daniel

Joyce Daniel, CPPB
Assistant Purchasing Agent

**#08ITB62600K-JD-T243 Reynolds Road at Westlake Parkway Intersection
Improvement
Addendum No. 2
Page Two**

This Addendum forms a part of the contract documents and **modifies** the original RFP documents as noted below:

Price Quote Form:

The Price Quote form has been revised. For Bid Form Price Quote submittals use Price Quote Form Attachment 1A.

Response to questions:

Question: On Sheet #5, Typical Section TS 4-Westlake Pkwy, Shows Asphaltic Concrete 25mm Superpave Asphalt @3 In Mix Design Level-B. Under Which Item, The Scope of Work will be Covered & Paid? There Is No Line Item of 25 mm Superpave Asphalt, Found In Bid-Schedule. Please, Clarify & Advise.

Response: A line item has been added. See Attachment 1A for revised Price Quote.

Question: On Sheet #14, Utility Plan, Regarding New Fire Hydrant, Who Will Take care of New Fire Hydrant & Installation of 12"x6" Tapping Sleeve? Utility Company or General Contractor? Is Covered Under Scope of Work or Not? There Is No Line Item, Included In Bid-Schedule. Contractor needs to Coordination only, or Not? Please, Clarify & Advise.

Response: There is no line item for utility relocations. Utility companies should relocate utilities and contractor shall coordinate utility relocations in accordance of sheet 4.

Regarding Storm Drainage, On Sheet #8 & Sheet #12, I Did Not Found Storm Drainage Manhole On Plan. At Which Location, Is to be constructed? Bid Schedule, Includes, Storm Sewer Manhole, Tp-1. Is It Covered Under Scope of Work or Not?

Response: Storm Sewer Manhole Type 1 refers to the Double Wing Catch Basin that will be constructed at STA 10 + 70 Sandtown Center Blvd. Yes, it is covered under scope of work.

**#08ITB62600K-JD-T243 Reynolds Road at Westlake Parkway Intersection
Improvement
Addendum No. 2
Page Three**

Question: Regarding Storm Drainage, On Sheet #12-Drainage Profile, Shows 18" RCP Safety End Section, but Not Included In Bid-Schedule item. Is It Covered Under Scope of Work or Not? Please, Clarify & Advise.

Response: A line item has been added. See Attachment 1A for Revised Price Quote.

Question: Would you please, clarify the following questions for the above mentioned project:

Bid Documents call for 90 available days for completion of project but note on Traffic Detour Plan Drawing #8-01 says Reynolds Road, Westlake Drive and Sandtown Center Parkway shall not remain closed for more than 120 working days.

Response: 90 Available days refers to completion of project. The 120 Days is revised to Calendar Days not working days as specified in the Detour Plan.

Roadway cross-section TS-02 between stations 1+19 to 4 + 95 on Drawing #5-01 call for new concrete sidewalk and curb & gutter on both sides of Reynolds Road but Drawing # 9-01 shows new concrete sidewalk and curb & gutter only on right side of Reynolds Road.

Response: Proposed sidewalk will only be constructed on the East Side of Reynolds Road.

Attachment 1A

Revised Price Quote Form

SECTION II: BID COCUMENTS

Bidder shall utilize the following revised Price Quote Form – Attachment 1A to submit price quote. Bidders shall enter all unit prices, make all extensions and total the Bid.

SECTION II: BID DOCUMENTS

PRICE QUOTE

Bidder shall utilize the following to submit price quote

ITEM #	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT COST	TOTAL COST
	ROADWAY ITEM				
150-1000	TRAFFIC CONTROL-T243	LS	Lump		
207-0203	FOUND BACKFILL-MATL TP	CY	20		
210-0100	GRADING COMPLETE-T243	LS	1		
210-250	UNDERCUT EXCAVATION PER SPECIFICATION 210-561	CY	750		
310-0101	GR AGGR BASE CRS. INCL MATL	TN	1125		
402-3121	RECYCLED ASPH CONC 25 MM, GP 1 or 2, INCL BITUM MATL & H LIME	TN	78		
402-3131	RECYCLED ASPH CONC 9.5MM, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	230		
402-3190	RECYCLED ASPH CONC 19MM SUPERPAVE, GP 1 OR 2, BITUM MATL & H LIME	TN	280		
413-1000	BITUM TACK COAT	GL	400		
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	1025		
441-0104	CONCRETE SIDEWALK, 4 IN	SY	215		
441-6222	CONCRETE CURB & GUTTER, 8 IN X 30 IN, TP 2 CLASS B CONCRETE, BASE OR PAVEMENT WIDENING	LF	510		
500-9999	SAFETY END SECTION 18 IN, STORM DRAIN , 4:1 SLOPE	CY	10		
550-3318		EA	1		
668-1100	CATCH BASIN, GP 1	EA	1		
668-1110	CATCH BASIN, GP 1, ADDL DEPTH	EA	1		
668-4300	STORM SEWER MANHOLE, TP 1	EA	1		
		SUBTOTAL			
	EROSION CONTROL				
163-0551	CONSTRUCT, MAINTAIN AND REMOVE INLET SEDIMENT TRAP	EA	2		
161-1000	EROSION CONTROL - T243	LS	1		
163-2100	CONSTRUCT, MAINTAIN AND REMOVE TEMPORARY DITCH CHECKS	EA	4		
171-0030	CONSTRUCT, MAINTAIN AND REMOVE TEMPORARY SILT FENCE, TP C	LF	1250		

T243 Reynolds Road at Westlake Parkway Intersection Improvement
ITB No 08ITB62600K-JD

ITEM #	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT COST	TOTAL COST
603-2181	STONE DUMPED RIP RAP, TP3, 18 IN	SY	40		
603-7000	PLASTIC FILTER FABRIC	SY	40		
700-0200	GRASSING - COMPLETE - T243	LS	1		
716-2000	EROSION CONTROL MATS, SLOPES	SY	1600		
		SUBTOTAL			
	SIGNING & MARKING				
636-1031	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	51		
653-0120	THERMOPLASTIC PAVEMENT MARKING ARROW, TP 2	EA	5		
653-1501	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN. WHITE	LF	2035		
653-1502	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN. YELLOW	LF	3065		
653-1704	THERMOPLASTIC SOLID TRAFFIC STRIPE, 24 IN. WHITE	LF	50		
653-1804	THERMOPLASTIC SOLID TRAFFIC STRIPE, 8 IN. WHITE	LF	1060		
653-3501	THERMOPLASTIC SKIP TRAF STRIPE, 5 IN. WHITE	GLF	335		
653-6004	THERMOPLASTIC TRAFFIC STRIPING, WHITE	SY	235		
654-1001	RAISED PVMT MARKERS TP 1, TP 2 AND TP 3	EA	22		
		SUBTOTAL			
	MISCELLANEOUS LANDSCAPING	ALLOW	LUMP	\$20,000.00	\$20,000.00
	TESTING ALLOWANCE	ALLOW	LUMP	\$10,000.00	\$10,000.00
		TOTAL			

BIDDERS SHALL ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS, AND TOTAL THE BID

ACKNOWLEDGEMENT OF ADDENDUM NO. 2

The undersigned proposer acknowledges receipt of this addendum by returning one (1) copy of this form with the proposal package to the Purchasing Department, Fulton County Public Safety Building, 130 Peachtree Street, Suite 1168, Atlanta, Georgia 30303 by the RFP due date and time **Monday, August 18, 2008, 11:00 A.M.**

This is to acknowledge receipt of Addendum No. 2, _____ day of _____, 2008.

Legal Name of Bidder

Signature of Authorized Representative

Title