
PROPERTY OWNER





CONCRETE COLLAR

METER

8" GRAVEL (#57 STONE)

PRE-CAST

METER VAULT

VAULT PLAN VIEW

VAULT ELEVATION VIEW

MANHOLE STEPS

AT 12" O.C.

CAST-IN-PLACE


ALUMINUM HATCH

24"

PROVIDE DUCTILE IRON FLANGED ADAPTER BETWEEN METER

ASSEMBLY AND GATE VALVE

(SEE SPECIFICATIONS)



- ANCHOR COUPLING REQUIRED

FROM NPRL

- FLOW

RETAINER GLANDS

W/ SET SCREWS 6" O.C. (TYP.)

EDGE OF R/W PREFERRED

LOCATION

AT STUB END

NOTES:

- BOXES EXCEEDING 5' DEPTH MUST BE APPROVED BY FULTON
- 2. WHEN METER BOX CANNOT BE LOCATED ENTIRELY ON R/W, A PERMANENT EASEMENT SHALL BE OBTAINED TO PREVENT FENCES OR OTHER OBSTRUCTIONS FROM BEING ERECTED AROUND THE METER BOX.
- 3. COVER OPENING & STEPS TO BE PLACED NEAREST THE METER REGISTER.
- 4. THE METER MUST BE INSTALLED WITH AT LEAST 8 DIAMETERS OF STRAIGHT PIPE SAME SIZE AS METER ON THE INLET SIDE TO PERMIT ON-SITE MAINTENANCE AND CALIBRATION, A STRAINER MAY BE PROVIDED IN LIEU OF THE STRAIGHT PIPE IN ACCORDANCE WITH THE METER MANUFACTURER'S RECOMMENDATIONS, AN INLET AND OUTLET GATE VALVE WITH BYPASS LINE ARE REQUIRED (SEE ILLUSTRATION).
- 5. THESE BOXES ARE ARE NOT TO BE INSTALLED IN TRAFFIC AREAS WITHOUT PRIOR PERMISSION FROM FULTON COUNTY.
- ALL VALVES AND FITTINGS INSIDE THE VAULT SHALL BE FLANGED.
- ALL FITTINGS OUTSIDE THE VAULT SHALL BE PUSH-ON JOINT WITH AMERICAN 'FAST-GRIP' GASKETS OR APPROVED EQUAL.
- ALL METERS SHALL COME EQUIPPED WITH A TOUCHREAD OR TOUCHLESS SENSOR COMPATIBLE WITH FULTON COUNTY'S METER READING EQUIPMENT.
- 9. THIS DETAIL ALSO AUTHORIZED FOR INSTALLAITONS OF 3" AND LARGER RE-USE METERS.
- 10. HATCH SHALL BE 4' X 6', DOUBLE LEAF, FLUSH MOUNT, $\frac{1}{4}$ " DIAMOND PLATE, ALIMINUM DOORS LOCKABLE WITH A $\frac{5}{8}$ " ROD. HATCH SHALL BE BILCO #PDCM-3 OR PRE-APPROVED EQUAL FOR 6" & 8" METERS.
- 11. HATCH SHALL BE 3'6" X3'6" SINGLE LEAF FLUSH MOUNT ¹/₄" DIAMOND PLATE, ALUMINUM LOCKABLE WITH \$" ROD. HATCH SHALL BE B.LCO#PCM - 5 OR PRE-APPROVED EQUAL FOR 3" & 4" METERS.